

## दर भाउ पेश गर्ने बरि को सुचना

प्रथमपटक प्रकाशित मिति: २०८२/१२/३०



१. काठमाडौं उपत्यका खानेपानी लिमिटेड त्रिपुरेश्वर शाखा अन्तर्गत तपशिलमा उल्लेखित कार्य गर्नुपर्ने भएकोले नेपाल सरकारको सम्बन्धित कार्यलयमा दर्ता भई निर्माण सम्बन्धी काम गर्ने इजाजतपत्र, २०८२/१८३ फर्म नविकरण प्रमाणपत्र, स्थायी लेखा नं. मू.अ.कर दर्ता प्रमाणपत्र, आ. ब. २०८१/८२ को कर चुक्ता प्रमाणपत्र र आ.ब. २०८२/८३ यस कम्पनीमा सुचिकृत भएका इच्छुक फर्म, संस्था, वा सेवा प्रदायकले प्रथम पटक प्रकाशित सुचनाको मितिले ३ दिन भित्र यसै सुचना सँगै रहेको दरभाउ शाखाको प्राविधिक फाटमा बुझाउनु पर्ने हुन्छ ।

२. मिति २०८३/०१/०२ गते ४:०० बजे सम्म दर्ता भएका दरभाउ सोहि दिन ५:०० बजे यस शाखा कार्यालयमा खोल्ने छ । दरभाउ फाराम बुझाउने अन्तिम दिन सार्वजनिक बिदा परेमा त्यसको भोलीपल्ट कार्यालय खुलेको दिन सोही अनुसार हुने छ ।

३. दरभाउ स्विकृत गर्ने वा आंशिक रुपमा स्विकृत गर्ने वा नगर्ने सम्पूर्ण अधिकार यस कम्पनीमा निहित हुनेछ ।

४. यस सुचनामा उल्लेख गरिए बाहेक अन्य कुराहरु सार्वजनिक खरिद ऐन २०६३ (संसोधित) र सार्वजनिक खरिद नियमावली २०६४ (संसोधित) तथा अन्य प्रचलित कानून बमोजिम हुनेछ ।

तपसिल

सि.न	कार्य विवरण	कार्य सम्पन्न अवधि	कार्य स्थान	दरभाउ पेश गर्ने अन्तिम मिति	कैफियत
१	Landscape Beautification and Aesthetic Enhancement of office Compound	२५ दिन	त्रिपुरेश्वर कार्यालय	२०८३/०१/०२	

यस सम्बन्धमा विस्तृत जानकारीका लागि कार्यालय समयमा यस कार्यालयको प्राविधिक फाटबाट बुझ्न सकिने छ ।

.....  
ई.सुरेन्द्र बहादुर रावल  
कार्यालय प्रमुख



**KATHMANDU UPATYAKA KHANEPANI LIMITED**  
**TRIPURESHWOR BRANCH OFFICE**

**QUOTATION**

**Project: Landscape Beautification and Aesthetic Enhancement of office Compound**

**Location: Tripureshwor Branch Office**

S.N.	DESCRIPTION OF WORKS	QUANTITY	UNIT	RATE		AMOUNT	REMARKS
				IN FIGURE	IN WORDS		
1	Transportation of Different Garbage	2.00	Trip				
2	Earth work for filling in foundation, trenches with proper compaction all complete works as per the instruction of site engineer.	7.35	m3				
3	Dismantalling of PCC Interlocking Cement Concrete Block for Pipeline Laying as per the instruction of site incharge.	7.50	m2				
4	Reinstatement of PCC Interlocking Cement Concrete Block Using Old as per the instruction of site incharge.	7.50	m2				
5	First class Brickwork in cement sand mortar (1:4) with all complete works as per drawing, specification and instruction of the Engineer.	1.30	m3				
6	Cement Sand Plastering Work of 12.5mm thick in 1:4 Cement Sand ratio all complete works as per drawing, specification & instruction of the Engineer.	14.40	m2				
7	Manual removal of old painting surface and carting away debris to all leads and lifts all complete work as per instruction of the Engineer.	120.00	m2				
8	Applying two or more coat of Weather Resistant Paint on external wall and ceiling surface over one coat of primer to give an even and uniform shade of approved color for external surfaces as per drawing, specification & instruction of the Engineer all complete.	242.50	m2				
9	Flat Brick Soling Work for floor treatment as per drawing and instruction of the Engineer with all lead and all lift.	8.76	m3				
10	PCC (1:2:4) work on floor including curing all complete as per instructions of site incharge.	4.36	m3				
11	Supply and plantation of different outdoor flowering plants all Complete Work	1.00	job				
12	Supply of cement concrete flower pots providing drainage hole, painting with and placing at site.	10.00	no				
	In words :Nrs.						
					Sub-Total		
					VAT@13%		
					Grand Total		

Name of Contractor:  
Signature and Stamp:  
Date: